


IND. TERR. ILL. OIL  
Burchart No. 2

SEC.14 T.20 R.11W  
Gen S $\frac{1}{2}$  S $\frac{1}{2}$  NE $\frac{1}{4}$

Total Depth, 3314  
Comm. 8-18-36 Comp. 9-15-36  
Shot or Treated.  
Contractor.  
Issued. 1-23-37

County. Barton



CASING:

12 $\frac{1}{8}$ " 203'  
7" 3280'

Elevation.

Production. Pot. 147 B.  
after acid.

Figures Indicate Bottom of Formations.

sand	87
shale	110
shale, shells & red bed	220
red bed	230
sand	300
red bed	474
anhydrite	494
shale & shells	799
shale & salt	1053
shale & shells	1145
lime & shale streak	1250
brkn lime	1350
lime	1375
brkn lime	1397
lime	1469
shale & shells	1677
sticky shale & lime shells	1747
lime	1760
shale	1797
shale & shells	1814
shale	2078
brkn lime	2150
shale & lime shells	2237
shale	2370
brkn lime	2455
sdv shale	2550
lime	2565
brkn lime	2655
lime	2720
brkn lime	2732
lime	2860
brkn lime	2877
Corr 2877=2876	
brkn lime	2940
shale	2995
lime	3270
lime	3280
cored	3286
shale	3290
dolomite-core sample	3295
lime stained	3302
lime	3309
sand gas	3311
lime white	3314
Total Depth	3314