

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Hurdock, Wichita, Kansas


Company - HOUSER DRLG. CO. ET AL
Farm - Burchart No. 3

SEC. 14 T. 20 R. 11W
SW ST NE

Total Depth. 3347
Comm. 7-24-49 Comp. 8-6-49
Shot or Treated.
Contractor. Houser Drlg. Co.
Issued. 10-1-49

County. Barton

KANSAS



Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar	5
sand, gravel	60
shale blue	170
red bed	482
anhyd.	495
shale & shells	970
salt	1220
shale & shells	1325
lime & shale	1660
Florence flint	1685
lime & shale	2140
shale & shells	2385
lime & shale	2620
lime	2950
lime & shale	3029
lime	3287
Congl.	3289
Arbuckle lime	3347
Total Depth	

Tops:	
K. C. lime	3043
Arbuckle	3289

Cable Tool:

Drilled cem & shoe - run line at
3273 $\frac{1}{2}$ drilled ahead 3287-3302 lime
3302-3328 "
3328-3347 "

bailing hole dry- hole caving run line at
3340'

run tubing - swabbing & bailing
12' fluid in hole all wtr.