


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- J. O. WILLIAMS
Farm- Langfield No. 7

SEC. 11 T. 20 R. 11W
CN/2 SW SW

Total Depth. 3281'
Comm. 1-11-52 Comp. 1-19-52
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 3-19-55

County Barton
KANSAS



Elevation. 1761'

Production. 28 BO & 75% wtr.

CASING:

8 5/8" 288' cem w/200 sx
5 1/2" 3280' cem w/150 sx

Figures indicate Bottom of Formations.

sand & gravel	140
shale & red bed	250
shale, red bed & shells	288
red bed & shells	545
anhydrite	558
shale & shells	990
shale, shells & salt	1310
shale & shells	1465
shale & lime	1680
lime	1730
lime & shale	2400
shale & shells	2661
lime & shale	2722
lime	2883
lime & shale	3113
lime	3225
lime & shale	3275
lime	3281
Total Depth	

Tops:

Anhydrite	545
Heebner	2876
Brown Lime	2997
Lansing	3023