


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- C.E. ASH ET AL
Farm- George Brenn "A" No. 1

SEC. 15 T. 20 R. 11W
NW SW SE.

Total Depth. 3330'
Comm. 5-1-56 Comp. 5-13-56
Shot or Treated.
Contractor. BEA Drlg. Co.
Issued. 7-21-56

County Barton
KANSAS



CASING:

8 5/8" 275' w/135 sx cem.
5 1/2" 3330' w/75 sx cem.

Elevation. 1678' DF

Production. 100 BO

Figures indicate Bottom of Formations.

sand	40
clay	70
sand-clay	94
shale	275
red bed	500
Anhydrite	525
shale-shells	645
red bed-shale	1000
salt	1200
shale-lime	1720
sdv lime	2160
shale-lime	2705
lime	2890
shale-lime	3020
lime	3155
lime-shale	3160
lime	3330
Total Depth	

TOPS: RB 1' above DF

Anhydrite	500
Heebner	2908
Douglas	2940
Brown lime	3030
Lansing	3049
Arbuckle	3303

Lansing show oil 3098-3133
DST fr 3094-3113 open 1 hr.
weak blow for 9 min. Rec. 10'
oil spotted mud. BHP 140#.

Kansing light show oil 3115-3156
DST fr 3135-3155 open 1 hr. fair
blow throughout test. Rec. 35'
thin OCM. 195' gas in drill
pipe. B HP 240#.

Arbuckle Cored fr 3305-3330

Rum Gomeray Log.

Perf. fr 3305-3308 w/24 shots.
Acidized w/1000 gal. Swabbed
1 hr. Made 20 bbls oil. NW.

Put on pump.