

GULF OIL CORP.
 Henry C. Langfeld No. 1.

SEC. 15 T. 20 R. 11 W
 NEc SE

Total Depth. 3311'
 Comm. 12-6-42 Comp. 3-1-43
 Shot or Treated.
 Contractor.
 Issued. 4-24-43

County. Barton



CASING:
 10³/₄" 226' Cem. LI
 7" 3299¹/₂' Cem. (P 2234, LI 1065¹/₂)

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	0-10	Acidized: 1-1-43 with 1000 Gals. 3299 ¹ / ₂ -3310
sand & gravel	60	(jetted formation)
sand & lime	100	Acidized: 1-2-43 with 1000 Gals.
shale & red bed	230	Acidized: 1-5-43 with 2000 Gals.
redrock & shells	550	
shale & shells	1360	
shale & lime	1445	
lime	1545	
lime & sand	1705	
lime	1775	
shale	1875	
lime & shale	2075	
shale	2170	
shale & lime	2385	
lime brkn	2450	
shale & lime shells	2520	
shale & lime	2640	
lime brkn	2675	
lime	2895	
lime & shale	2940	
shale & shells	2995	
shale & lime	3035	
lime	3298	
Arbuckle lime	3311	
Total Depth.		

Top Lansing 3047
 Arbuckle lime 3298-3311