


STANOLIND OIL & GAS CO.
L. Hauser No. 6-B.

SEC. 16 T. 20 R. 11W
CSE NW
660' N SL 1980' E WL NW $\frac{1}{4}$

County, Barton



Total Depth. 3295'

Comm. 3-31-40

Comp. 4-22-40

Shot or Treated.

Contractor.

Issued. 7-13-40

Rotary O-3293

Cable 3293-95

CASING:

10 $\frac{3}{4}$ "

212' 2"

5 $\frac{1}{2}$ "

3289'

Elevation.

Production. Pot. 382 B. Physical
no wtr

Figures Indicate Bottom of Formations.

sand	80
shale & shells	150
lime hrd & iron	
pyrite	154
shale & shells	180
shale	225
shale & shells	250
red bed	485
anhydrite	520
shale & shells	880
salt & shells	890
salt	943
shale & shells	1425
lime	1450
lime brkn	1465
lime	1630
shale & lime	1680
shale	1720
lime	1750
lime brkn	1895
lime	1958
sand sft	1968
lime	2055
shale & lime	2200
shale	2410
lime brkn	2665
lime	2930
shale	3030
lime	3045
lime brkn	3100
lime	3205
lime(oil odor in samples)	3210
lime	3267
shale	3288
dolomite	3295
Total Depth.	

Arbuckle dolomite 3288-95

Initial test - 9 BPH off btm
Physical potential 382 BPD,
no wtr