

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

GULF OIL CORPORATION
Peter Schartz No. 4

SEC. 18 T. 20 R. 11 W.
NE SE SW

Total Depth. 3365
Comm. 11-28-41 Comp. 12-17-41
Shot or Treated.
Contractor.
Issued. 2-7-42

County Barton.



CASING.

85/8" 220' Cement

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

surface soil	40
sand and gravel	135
sticky shale	155
sand and shale	230
red bed	560
red bed and shells	735
shale and shells	870
red bed & shale	1030
shale and shells	1170
salt	1270
shale and salt	1350
shale and limo shells	1435
broken limo and shale	1520
shale and limo shells	1550
shale and limo	1625
broken limo	1650
sand	1654
broken limo	1735
limo	1813
limo and shale	1985
broken limo	2000
limo	2080
shale and shells	2180
shale and limo	2230
broken limo	2472
limo	2572
broken limo	2605
limo	2778
limo hard	2800
limo	2825
broken limo	2850
limo hard	2885
limo	2955
limo and shale	3025
shale	3060
limo	3156
Kansas City Lime	3190
limo and shale	3240
limo	3308
limo and shale	3328
conglomerate and chert	3342
limo	3362
dolomite and chert	3365
Total Depth.	

Top Conglomerate 3303
Arbuckle lime 3359-3365