


HOLLOW DRILLING CO. Inc.
 Kowalsky No. 4.

SEC. 18 T. 20 R. 11W.
 CN¹/₂ NE NE

Total Depth. 3307
 Comm. 9-15-40 Comp. 9-26-40
 Shot or Treated.
 Contractor. Hollow Drilling Co., Inc.,
 Issued. 11-2-40

County Barton.



CASING. Rotary with Cable.

85/8" 232' cemented.
 5 1/2" 3300' cemented.

Elevation.

Production. Pot. 8109 B.
 Echometer.

Figures Indicate Bottom of Formations.

sand	95
shale	165
shale	185
sand	215
shale lime shells	232
red rock shells	520
anhydrite lime	545
shale shells	770
shale and shells	1030
salt	1182
salt and shells	1340
lime	1350
shale and lime.	1450
lime	1547
lime	1630
shale and lime	1705
shale lime shells	1820
lime and shells	1924
lime	1935
shale and lime	1990
sand	2000
lime	2006
lime and shale	2115
lime	2258
lime and shale	2383
lime	2458
shale lime shells	2596
shale and lime	2620
lime	2640
shale and lime	2660
lime	2685
lime	2955
shale	2980
shale and lime	2995
shale	3061
lime	3115
KC. lime	3183
lime	3302
3302 equals 3299 Derrick floor correction SLM.	
Arbuckle lime	3301 HFO 2700' 2 hrs.
Arbuckle lime	3307

Total Depth.

Top Arbuckle dolomite 3302