

KOWALSKY WELL NO. 6

C W/2 NW/4 NE/4 Sec. 18-20-11W  
Barton County, Kansas

Date Commenced: March 24, 1941

Date Completed: April 7, 1941

Contractor: Hollow Drilling Company, Inc  
Inman, Kansas

Tools: Rotary Drilling Tools,  
Completed with Cable Tools.

Pipe Record

Ran 12 jts. 252' 8 5/8 SH 28#  
Pipe--Cemented with 100 Sx  
Regular, 25 Sx OilMax at 237'.

Ran 104 jts. new 5 1/2" 14# seamless  
pipe, cemented with 100 Sx  
Regular at 3308 1/2'.

0	90	Sand
90	190	Shale and shells
190	237	Shale and shells
237	620	Shale and lime shells
620	1100	Shale, shells, salt
1100	1260	Salt
1260	1400	Lime
1400	1448	Shale and lime shells
1448	1575	Lime and shale
1575	1635	Lime and shale
1635	1746	Shale and lime shells
1746	1905	Shale and lime shells
1905	2005	Lime and shale
2005	2100	Lime and shale
2100	2255	Shale and lime shells
2255	2395	Shale
2395	2510	Shale and lime shells
2510	2590	Shale and lime shells
2590	2680	Lime
2680	2765	Lime
2765	2825	Lime
2825	2880	Lime
2880	2920	Lime
2920	2940	Shale
2940	3006	Lime
3006	3054	Shale and lime
3054	3109	Lime
3109	3169	Lime
3169	3230	Lime
3230	3279	Lime
3279	3310	Lime
3310	3312	Arbuckle Top Arbuckle 3310' equals 3308' Derrick Floor
3310	3311	Arbuckle Dolomite
3311		T.D. SLM

Remarks

Hole filled 2600' oil no water in 1 hr - Swabbing from  
768' down well swabbed 19.6 bbls per hour.

Potential test 4/7/41  
Echometer - 3780 bbls, no water.