


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company. ISERN DRILLING CO., et al  
Farm- Dannebohm No. 1

SEC. 20 T. 20 R. 11W  
SW NW NE

Total Depth. 3339  
Comm. 8-4-55 Comp. 8-17-55  
Shot or Treated.  
Contractor. Isern Drilling Co.  
Issued. 10-29-55

County Barton  
KANSAS



8 5/8 @ CASING; 253' w/ 250 sx cmt.  
5 1/2 @ 3331' w/ 100 sx cmt.

Elevation. 1784 DF

Production. 40 BOPD

Figures indicate Bottom of Formations.

sand	130
shale & shells	250
red bed	535
anhydrite	550
shale & shells	1030
salt	1230
shale & shells	1450
lime & shale	2070
shale & shells	2620
lime & shale	2939
Heebner shale	2944
shale & lime	3067
lime	3324
Arbuckle	3339
Total Depth	

TOPS:	
Heebner	2940
Brown lime	3065
Kansas City	3085
Arbuckle	3325

Drl'd. plug & cmt. 3309-14, CO to 3339  
Swb. approx. 4 BOPH/8 hrs.