


MARGAY & HERNDON DRUG CO.
Hagan No. 2

SEC. 20 T. 20 R. 11 W.
SE NW SW

Total Depth. 3335
Comm. 1-13-42 Comp. 2-6-42
Shot or Treated.
Contractor.
Issued. 3-28-42

County Barton



CASING.

85/8" 263' cemented.
5 1/2" 3320 1/2 cemented.

Elevation.

Figures Indicate Bottom of Formations.

Production. Pot. 335 B.

cellar	11
surface	30
sand	152
shale and shells	190
shale and sand	220
shale and shells	263
red bed and shale	561
anhydrite	575
shale and shells	825
salt	1125
shale and shells	1490
broken lime	1615
broken lime	2055
broken lime	2145
shale and shells	2630
lime	3005
shale and shells	3050
lime	3075
lime and shale	3155
lime	3250
lime and shale	3320
lime	3335

Total Depth.

Top lime 3085
Top Arbuckle Corr. 3314