


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL CO.
Farm - C. Kasselmann No. 1

SEC. 22 T. 20 R. 11 W
NE o NW
330'S 330'W N $\frac{1}{2}$ cor.

Total Depth. 3364'GL
Comm. 9-25-44 Comp. 10-15-44
Shot or Treated.
Contractor.
Issued. 11-18-44

County. Barton
KANSAS



CASING:
13 3/8" 228' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	0-486
anhydrite	521
shale & shells	996
salt	1106
salt, shale & shells	1226
shale & shells	1421
shale & lime	1716
lime brkn	1896
lime	1951
lime & shale	2176
shale & shells	2256
shale & lime	2511
lime brkn	2601
lime & shale	2651
lime	2936
lime & shale	3016
lime	3364
Total Depth GL	

Tops:

KC Lime 3055
Arbuckle Lime 3313

10-13-44 Cored 3319-3324.

Rec. 2 $\frac{1}{2}$ ' of Arbuckle
lime w/small stain of
oil.

10-15-44 Deepened to 3364

in Arbuckle lime. Set
Packer @ 3314 & ran drill
stem test, recovering 30'
of mud - no show of oil.

Total depth 3364 in Arbuckle Lime.

10-16-44 P & A

Note: Footages calculated from
ground level.