

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORPORATION
Farm - Anna Kasselman No. 5

SEC. 23 T. 20 R. 11W
NE NW SW

Total Depth. 3288'
Comm. 2-19-47 Comp. 3-6-47
Shot or Treated. Acid. w/2000 gals. 3-4-47
Contractor.
Issued. 5-10-47

County. Barton
KANSAS



CASING:
8-5/8" 308' LI Cem. w/130 sx
5-1/2" 3278' LI Cem. w/100 sx

Elevation. _____

Production. 253 BO, No. wtr.

Figures Indicate Bottom of Formations.

sand	0-100
shale	130
shale & shells	165
shale & red bed	308
red bed	450
red bed & shale	1075
shale & salt	1275
shale & shells	1310
anhydrite	1420
shale & shells	1700
lime brkn	1775
shale & shells	2335
shale & lime	2770
lime	2957
shale & lime	3025
lime brkn	3190
lime	3288
Total Depth	

Sand Record:
Arbuckle 3276

Distance H: Top collar on 5 1/2"
to rotary table 3'.

Tops:
Hebner 2883
Douglas Shale 2916
Lime Brown 3008
Lansing 3031
Arbuckle 3276

Free oil 3284-86