

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

IND. TERR. ILL. OIL CO.
Alice Bryant No. 2

SEC. 23 T. 20 R. 11W.
SE NE SE
990' S NL 330' WEL SE $\frac{1}{4}$

Total Depth, 3316
Comm. 12-15-37 Comp. 12-29-37
Shot or Treated.
Contractor, Schoenfeld-Hunter-Kitch Drlg. Co.
Issued. 1-22-38

County Barton.


CASING. Rotary.

103 $\frac{1}{4}$ " 189'

Elevation.

Production, DRY.

Figures Indicate Bottom of Formations.



surface sand	10
sand and gravel water	80
shale and shells	160
red bed	199
shale and red bed red soft	575
shale and shells red mod	865
shale and shells red mod	1250
lime and shale blue hard	1330
lime and chalk wh med	1435
lime shale and shells red soft	1615
lime and shale blue mod	1650
sand white hard	1750
shale and lime	1820
shale and lime blue soft	1950
lime blue mod	2010
shale blue soft	2135
shale and lime blue mod	2285
shale blue mod	2365
lime brown mod	2450
shale blue soft	2500
shale blue mod	2570
lime brown hard	3000 checked meas. at 2670
lime and sand brown hard	3025
sand white mod	3040
lime blue mod	3135
lime blue hard	3190 checked meas. 3150
lime grey hard	3270
lime and chert grey hard	3275
chert grey hard	3285
lime and chert wh hard	3295
chert grey sharp	3310
chert grey soft	3313
lime and chert grey hard	3315
shale and chert brown soft	3318
S.L. corr. 3318 = 3316	
Total Depth	3316