

LARIO OIL & GAS CO.-ATLANTIC REFG. CO.
Poter No. 5

SEC. 24 T. 20 R. 11 W
SE NE NW

DEEPENING RECORD

Total Depth. 3745' 4"
Comm. 1-18-37 Comp. 4-26-37
Shot or Treated. 200 qts
Contractor. Broadwater Drlg. Co.
Issued. 6-5-43

County Barton.



CASING.

12 $\frac{1}{2}$ " 161' 8 $\frac{1}{2}$ " 3254

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

surface	19
sand	81
rod rock	153
red rock and shalo	430
shale and shells	917
salt and shalo	1243
shale and shells	1338
lime	1369
shale and shells	1551
lime	1585
brokon lime	1620
lime and shale	1658
shalo	1716
broken lime	1787
lime	1900
shale	1930
lime and shale	1987
shale	2002
lime	2038
lime and shale	2195
shalo and shells	2316
lime	2420
shale	2440
shale and lime	2507
lime	2540
shale and shells	2607
shalo	2627
lime	2749
shale	2786
lime	2847
shale and lime	2860
shalo	2885
shalo and lime	2935
shalo	3008
shalo and lime	3023
shalo	3026
lime	3136
brokon lime	3146
shalo	3157
shale and lime	3198
lime	3243
lime and shalo	3250
shale	3254
dolomite	3313
Total Depth.	

DEEPENING RECORD:

Lario Oil & Gas Co.
Comm. 11-8-42 Comp. 11-18-42
Salt Wtr Disposal Well
5 $\frac{1}{2}$ " 3410' Cem.

lime cherty	3520
chert	3575
chert & lime	3601
lime	3731
sand hd	3740
chert brown	3744' 6"
chat brown	3745' 4"
Total Depth.	

shot with 200 qts.
pipe collapsed
cemented 8 $\frac{1}{2}$ " at 2500
cleaned out.
S.O. in bailer at 3260 with 900' water in hole
Abd as dry hole

Top siliceous 3254
Cored 3250-55 $\frac{1}{2}$