

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

MAGNOLIA PETROLEUM CO.
H.J. Roetzel No. 21.

SEC. 24 T. 20 R. 11W.
CEL NE NE
660' FNL 330' FEL E $\frac{1}{2}$

Total Depth. 3251 SLM
Comm. 2-4-41 Comp. 2-25-41
Shot or Treated.
Contractor.
Issued. 4-12-41

County Barton.



CASING.

103/4" 246' cemented.
5 1/2" 3245' cemented. Corr.

Elevation.

Production. Pot. 5130 B.
no wtr Depthograph
Maximum Pot. 3000 B.
No wtr.

Figures Indicate Bottom of Formations.

sand and shale	160
shale and shells	246
red bed	280
shells and red bed	470
shale and shells	546
anhydrite	579
shale and shells	790
salt shale and shells	1100
shale and shells	1250
shale and lime	1470
shale	1525
sand	1540
shale and shells	1669
sand	1700
shale	1725
lime and shale	2275
shale and lime	2305
shale	2363
shale and shells	2402
shale	2585
lime	3005
shale	3013
lime	3256

Standardized

bailed hole and C/O to 3256

SLM correction 3256 equals 3247

At 3247 well making 1 bailer oil per hr - no wtr.

Arbuckle lime 3249

Filled to top in 2 hours.

Arbuckle lime 3251 SLM

Started flowing in 1/2 hour.

Total Depth.

Top of Arbuckle 3244 Corr.