


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

IND. TERR. ILL. OIL CO.
Rose Bryant No. 4.

SEC. 25 T. 20 R. 11W
CSL NW
330' fr SL 1320' fr WL NW/4

County. Barton

Total Depth. 3305'
Comm. 8-7-37 Comp. 8-26-37
Shot or Treated. 2000 Gals.
Contractor. Schoenfeld-Hunter-Kitch
Issued. 12-11-37 Rotary & Cable



CASING:
10" 194'
7" 3274'

Elevation.

Figures Indicate Bottom of Formations. Production, Pot. 514 B. after acid.

sand surface	90
sand & R.R.	194
shale	400
red bed & shale	675
shell & R.R.	885
shale	1130
shale & shells	1426
shale & salt	1700
shale & shells	1883
shale & lime	2063
shale & lime shells	2335
lime & shale	2457
shale	2625
lime	3272
sand	3275
lime	3305
Total Depth.	

Prod. 1st 8 hrs 514 Bbls. Pump
Produced on potential test after
acidizing w/ 2000 gallons.