


IND. TERR. ILL. OIL CO.
L. Schrepel No. 1-B.

SEC. 25 T. 20 R. 11W
NW 1/4 SW
330' fr NL 440' fr WL SW 1/4

County. Barton

Total Depth. 3325'
Comm. 6-4-37 Comp. 10-24-37
Shot or Treated.
Contractor. Mac & Stauffer Drlg. Co.
Issued. 12-11-37



CASING:

12 1/2" 206'
* 7 " 3295'
7 " 3298'

* At 3306' a fishing job was encountered.
Reclaimed 2196' of 7" osg., set whipstock
at 2160' and redrilled to 3325'

Elevation.

Production. Pot. 491 B.
after acid.

Figures Indicate Bottom of Formations.

sand	42
sand & gravel	132
sand & red rock	206
lime hrd	220
red bed & sand	300
sand & gravel, red	340
red bed	350
lime grey	400
shale	630
shale & shell	720
shale	900
shale & shells	950
lime	1005
salt	1205
lime grey	1480
sdv lime grey	1580
shale blk & blue	1603
lime grey	1830
lime sdv grey hrd	1880
shale blue	1930
shale	2037
shale blue sft	2225
lime grey	2315
lime	2440
shale blue sft	2450
lime hrd	2458
lime SLM	2470
shale blue sft	2530
lime	3325
Total Depth.	

Production 1st 10 hrs 372 bbls swab.
Prod. 491 bbls 8 hrs on potential
test after acidizing.