


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bldg., Wichita, Kansas.

MAGNOLIA PETRO. CO.  
Anna Roetzel No. 5.

SEC. 25 T. 20 R. 11W  
NW SW NE

Total Depth. 3277' SLM  
Comm. 2-20-38 Comp. 3-17-38  
Shot or Treated. 2000 Gals.  
Contractor.  
Issued. 4-30-38

County. Barton



CASING:  
13" 189'  
7" 3266'

Elevation.

Production. Pot. 1668 B.

Figures Indicate Bottom of Formations.

cellar	7
sand	80
shde	110
shale blue	140
red bed & shale	189
red bed, shale & shells	650
shale, shells, salt	1025
shale & salt	1285
shale & lime	2180
shale	2385
shale & lime	2525
shale	2620
lime	2845
shale & lime shells	2870
lime	3075
shale & lime	3185
lime	3250
cored 12' recovery	3250-68
Top Arbuckle	3265
Standardized	
Arbuckle lime	3269
Arbuckle lime-cored	
3269 to	SLM3277
Total Depth.	