


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILG. CO.
Farm- Sessler No. 5

SEC. 29 T. 20 R. 11W
CE/2 SE SW

Total Depth. 3403
Comm. 10-22-51 Comp. 11-1-51
Shot or Treated.
Contractor. Honaker Drilg. Co., Inc.
Issued. 12-29-51

County Barton
KANSAS



CASING:

8 5/8" 310' cem. w/225 sx
5 1/2" 3371' cem. w/135 sx

Elevation. 1820 DF

Production. Dry

Figures Indicate Bottom of Formations.

sand & top soil	70
sand	170
sand & shale	225
red bed & shells	310
shale & red bed	450
shale & shells	555
anhydrite	590
red bed, shale & shells	845
shale & shells	1045
shale, shells & salt	1155
shale & shells	1400
shale & lime	1455
lime	1694
lime & shale	1980
shale	2440
lime & shale	2585
shale	2686
lime & shale	2856
lime	3015
lime & shale	3057
lime	3165
lime & shale	3240
lime	3300
lime & shale	3364
lime (T.R.O.)	3374
lime	3403
Total Depth	

Tops:

Hebner	2971
Brown Lime	3097
Lansing-Kansas City	3117
Arbuckle	3370

DST: 3244-52' open 30 mins.
rec. 10' mud.

Perf. 24/3328-40 20 GWPH
28/3286-3300 no fld. Plug 3270
Perf. 36/3246-52 no fld. 500
tested 5 to 8 GWPH w/scum oil