


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BAY PETROLEUM CORPORATION et al
Farm- Sessler No. 3

SEC. 29 T. 20 R. 11W
SW NE SW

Total Depth. 3370
Comm. 1-28-52 Comp. 3-4-52
Shot or Treated.
Contractor. Pickrell Drilling Co.
Issued. 4-26-52

County Barton
KANSAS



Elevation. 1806

Production. Phy. 95 bbls

CASING:

8 5/8" 568' cem 2/325 sx.
5 1/2" 3353' cem w/100 sx.

Figures Indicate Bottom of Formations.

sand	100
sand, clay	220
red bed	550
chalk	560
anhydrite	567
shale	940
shale, salt	1405
lime sandy	1605
lime sdy & shale streaks	1725
lime	1840
shale, shells	2300
shale, lime	2465
shale, shells	2580
shale, lime	2740
lime	2815
shale, lime	2955
shale	3110
lime	3355RTD
D.P. DD. 2' to	3355
Show Oil	
D.D. Shale break	3366-67
D.D. Sli. inc. in	
oil. Hole caving	3368
D.D. 3 GOPH	3370
500 Acid 3 BOPH	
Total Depth	

Tops:
Heebner 2964
Brown Lime 3093
Lansing 3108
Arbuckle 3351

Circulate for samples at 3350
" " " " 3355

SLM 2055 OK
SLM 3200 OK
SLM 3356 - 1' correction