

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - ALEDO OIL & GAS & TRANSIT CORP.
Farm - Soeken No. 1

SEC. 30 T. 20
SW SW NW

11W

Total Depth. 3403
Comm. 6-22-49 Comp. 7-13-49
Shot or Treated. Acid
Contractor.
Issued. 8-13-49

County. Barton
KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" 315' cem W/200 sx.
5 1/2" 3383 1/2' cem w/100 sx.

Figures Indicate Bottom of Formations.

sand	100	small amount of gas will tools.
clay, shale	150	Dry and aband.
shale, red bed	260	
shale shells	315	Lane-Wells Measurements:
red bed, shale	485	Arbuckle top: 3385 D.F. - 3387 K.B.
shale, shells	1110	5 1/2" casing 3388' DF 3390 K.B.
salt	1230	Bottom hole : 3389 D.F. 3391 K.B.
shale, shells	1500	
lime, shale	2270	
shale, shells	2495	
lime, shale	2735	
lime brkn	2815	
lime, shale	2920	
lime	3125	
lime, shale	3166	
lime RTD	3387	

CABLE TOOL INFORMATION

Perf. w/4 shots thru shoe
Shot from 3382 1/2 - 3385
1st shot 3385 1/2 - 87 1/2, 8 shots
2nd shot 3386 - 88, 8 shots, acid
w/1000 gals. no result.
1st run VC shale 3390 - 3391
2nd run VC shale 3391 - 3397
lime small amt shale, inc of
stain poor porosity 3401
porosity, stain decreased to
lgt colored lime, no inc in
oil. Inc. in water 3403
Total Depth

Tops:
Arbuckle 3385 D.F.
3387 K.B.

7-8-49, Set LaneWells plug,
per forated 3226-3233, considerable
mud, slight oil stan. Bailed 1 1/2 gals
water w/film oil, fair porosity,
no stain. 12 hr fillup 54 gals.
water, 2 gals. heavy blk oil,
Perforated: 3163 1/2 - 67 1/2 D.F. 12
shots, no results.
Perforated 3147 - 3152 DF 15 shots
no results. Continued to make
about 1 1/2 gals water and scum oil
thru all tests.
Perforated 3155 - 3158 D.F.
9 shots, no results.
Arbuckle: was acidized w/1000 gals.
acid. No results except gas following
tools.
7-10-49, 50' fluid hole, 1 gal heavy
blk oil. 7:00 am
1 gal water 1 pint live oil good odor.
1000 gal acid in hole @ 11:00 am.
7-11-49, 200' fluid in hole, 6 gal oil
some dead flaky oil found in water,