

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.
Farm - Jutting No. 3

SEC. 30 T. 20 R. 11W
NE S SE

Total Depth. 3380' D.F.
Comm. 8-13-48 Comp. 9-27-48
Shot or Treated. Acidized
Contractor. Gabbart & Lindas Drlg. Co., Inc.
Issued. 10-23-48

County. Barton
KANSAS



CASING:

-5/8" OD 565' 5-1/2" OD 3366'

Elevation. _____

Production. 188 BO, plus 4% wtr.

Figures Indicate Bottom of Formations.

collar	8
sand	275
red bed	495
red beds & sand	568
anhydrite	595
red bed & shale	825
shale & shells	1110
salt & shale	1455
shale & lime	1580
shale & shells	1610
lime brkn	1790
lime	1860
lime & shale	1955
lime brkn	2120
shale & lime	2285
shale	2400
lime	3025
shale	3145
lime	3363
shale	3370
arbuckle & lime RTD	3373
arbuckle	3380 DF
Total Depth	

Tops:
Lansing 3129
Simpson 3358
Arbuckle 3366

DST 3366-69 op. 15" Rec. 100'
md, 3 oil. DP to RTD - VISO
2 Bbls. acid, 1 qt free oil.
500 acid - Swab 1 BOPH/5 hrs.
DD 2' no increase, 1000 acid,
no inc. DD 9' no inc. 10 qts
N.G. 1500 acid - swab 2 BOPH
no water.