


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- BAY PETRO. CORP. ET AL  
Farm- Jutting No. 7

SEC. 30 T. 20 R. 11W  
NW SW SE

Total Depth. 3351  
Comm. 3-27-52 Comp. 5-12-52  
Shot or Treated.  
Contractor. Pickrell Drlg. Co.  
Issued. 7-12-52

County Barton  
KANSAS



Elevation. 1808

Production. Phy. Pot. 210 BOPD

CASING:

8 5/8" 570' cem. w/350 sx circ.  
5 1/2" 3345' cem. w/100 sx

Figures Indicate Bottom of Formations.  
Meas. from top rotary bushing.

sand & clay	220
shale & red bed	565
anhydrite	587
shale & shells	1050
salt & shale	1490
shale & shells	1705
lime & shale breaks	1870
lime & shale	2035
shale & shells	2270
lime & shale	2572
shale & shells	2725
lime	2880
lime hrd	2925
lime	3346
lime	3351
Total Depth	

Tops:  
Anhydrite 565  
Lansing 3116  
Arbuckle 3342

RTD 3344'

DP & CO to TD 350' OIH/12 hrs.  
swab 1 BOPH. DD 3346 swab 13/4  
BOPH. DD 3347 no inc. 500 acid.  
DD 3349 no inc. DD 3350 inc. gas  
& oil. DD 3351 Swab 6.5 BOPH no wtr.  
swabbed 12 hrs. @ 10 BOPH no wtr.  
Circulate for samples at 3340'  
Circulate for samples at 3346'