

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - BAY PETROLEUM CORP. & ANDERSON-PRICHARD
Farm - Kowalsky No. 2

SEC. 32 T. 20 R. 11W
NW SE NW

Total Depth. 3410 $\frac{1}{2}$
Comm. 5-17-49 Comp. 6-29-49
Shot or Treated. acid
Contractor. C. E. Ash
Issued. 8-27-49

County. Barton
KANSAS



CASING:
8 5/8" 582' cem w/350 sx.
5 1/2" 3373' cem w/100 sx.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	200
clay	255
red bed	573
anhydrite lime	589
red bed	730
shale blk	890
shale, shells	1140
salt	1300
shale	1380
lime	1480
lime, shale	1880
lime	1940
lime, shale	2940
lime	3000
lime shale	3165
lime	3377
lime	3410 $\frac{1}{2}$
Total Depth	

Tops:
Brown lime 3108
Lansing 3124
Arbuckle 3372

500 acid - DD 9' to 3386',
1 $\frac{1}{2}$ BWPH and scum oil.
PB 3380, 10 qts. nitor., N.S.
500 acid, DD 3394, 1 $\frac{1}{2}$ GPH.
DD 3396, no help.
DD 3398, no help
DD 3410 $\frac{1}{2}$, 4BWPH, plus scum oil