

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - KEYES DRILG. CO., ET AL
Farm - Hagen No. 1

SEC. 34 T. 20 R. 11 W
CSL SW NE

Total Depth. 3351'
Comm. 7-19-46 Comp. 7-24-46
Shot or Treated.
Contractor.
Issued. 8-24-46

County. Barton

KANSAS



Elevation. _____

Production. Dry

CASING:
8 5/8" 204'
5 1/2" - 3324'

Figures Indicate Bottom of Formations.

clay ~ sand	0-154
shale blue	185
red bed	200
red bed, sand & shale	505
anhydrite	535
shale & shells	1475
lime	1545
lime & shale	1945
shale & shells	2120
shale	2570
shale & shells	2695
lime	2930
lime & shale	3005
shale	3063
lime	3328

Total Depth w/rot.

Moved in cable tools
drld cem., cleaned
out & drld. deeper.

lime	3347
sand	3351

Total Depth

Tops: Corr. 3' to DF

Topeka	2664
Heebner shale	2916
base Oread	2947
Brown lime	3049
Lansing	3069
Arbuckle	3320