


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

D.R. BUCHANAN ET AL.
Langfeld No. 1-B.

SEC. 14 T. 20 R. 11W.
CNL SE SW

Total Depth. 3290
Comm. 7-11-40 Comp. 7-23-40
Shot or Treated.
Contractor. Gerbrand-Pulse Oil & Drlg. Co.
Issued. 9-14-40

County Barton.



CASING.

85/8" 223' cemented.
5 1/2" 3278' cemented.

Elevation.

Production. Pot. 3250 B.

Figures Indicate Bottom of Formations.

surface sand	75
red bed, iron pyrites	190
shale red	775
shale and shells	1490
lime	1600
shale and shells	1695
sand	1710
shale	1800
lime	1920
broken lime	2025
shale	2330
lime	2355
shale and shells	2455
shale	2480
lime	2525
shale and shells	2585
lime	2775
broken lime	2845
lime	3185
broken lime	3245
shale and shells	3278
Arbuckle lime	3290

Total Depth.

First oil at 3278 to 82