

March 1934

Midwest #29 Scheufler,
C SW SE, 9-20S-11W,
Elevation 1767'

1773 DF₂ (Printed)

Pennsylvanian conglomerate Rotary to top of dolomite. Price reports
no conglomerate but marine beds lying on dolomite.

Ordovician	Top 3304'		Sub-sea, minus 1537'
Arbuckle	Top 3304'	Penetration 30'	" " " "
	3304-3334'	Exact correlation questionable. Either Cotter of Purcell, possibly the Purcell-Cotter contact is present.	

Remarks: This well appears to be some distance, a matter of miles,
from the pre-Pennsylvanian outcrop of the Decorah. At least 35' of
Miller and Purcell are missing and abundant banded secondary chal-
cedony speaks for the exposure of the Arbuckle for a considerable
period of time.

The lack of conglomerate indicates a high topographic position.

More wells will be required to clear the details of correlation in
this area. The Isern area, to the east, has been correlated in
considerable detail because three offset wells are available. No
one of these are clearer than the above well, but the combination of
three allows a more detailed picture to be made.