

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. SKELLY OIL CO.
Farm. Opal Lanterman No. 6

SEC. 16 T. 20 R. 12W
C W/2 NE SW
660' fr NL, 990' fr EL, SW/4

Total Depth. 3430
Comm. 5-21-57 Comp. 5-31-57
Shot or Treated. 500 gal acid 3423-30
Contractor. Claude Wentworth Drilling Co., Inc.
Issued. 8-3-57

County Barton

KANSAS



Elevation. 1844 DF

Production. 150 BOPD

CASING:

8 5/8 @ 651' w/ 400 sx cmt.
5 1/2 @ 3423' w/ 125 sx cmt.

Figures indicate Bottom of Formations.

surface soil, sand & clay	355
shale & red bed	640
anhydrite	655
shale & shells	1810
shale & lime	3316
conglomerate & lime	3420
brown sucrosic dolomite	3430
Total Depth	

TOPS:

Heebner	3042
Toronto	3056
Douglas sand	3074
Brown lime	3162
Lansing	3178
Conglomerate	3410
Arbuckle	3420

DST #1: packer @ 3404, 26' anchor,
open 1 hr. rec. 35' SO&GCM, IFP 25#,
FFP 25#, BHP 100#/20 min.

Producing Formation: Arbuckle 3423-30