


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

Company - C. U. BAY
 Farm - Batchman No. 1

SEC. 18 T. 20 R. 12W
 NW NW NE

Total Depth. 3422
 Comm. 2-15-49 Comp. 4-18-49
 Shot or Treated. Acid.
 Contractor. Pickrell Drilling Co., Inc.
 Issued. 5-14-49

County. Barton
 KANSAS



CASING:
 8 5/8" 360' cem w/250 sx.
 5 1/2" 3419' cem w/150 sx.

Elevation. _____

Production. 190 BOPD

Figures Indicate Bottom of Formations.

surface sand, clay	60
sand, iron	140
shale	180
shale, shells	335
red bed	360
red rock	650
anhydrite	675
shale, shells	1625
lime, shale	1890
lime	1955
shale	2020
lime, shale	2205
shale, shells	2365
shale, lime	2510
shale, shells	2565
lime, shale	2745
lime brkn, shale	2830
lime	2895
shale, lime	3190
lime	3345
lime, shale	3408
lime	3422
Total depth	

Tops:

Br. Lime	3157
Lansing	3171
Arbuckle	3418

Perf. 24 shots 3194-99
 " 24 shots 3204-08

1000 acid, swbd well in,
 did not flow, swbd 1000' oil
 pr hr thru 5 1/2" casing.

Pmp 6 BOPH.

1625, slope test @ 1000-1500' OK
 2020, slope test @ 2000' OK
 2510' slope test @ 2500' OK
 3190' slope test @ 3000' OK
 3422 slope test OK