

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


Company - C. U. BAY
 Farm - Huschka

No. 1

SEC. 18 T. 20 R. 12W
 NE NE NW

Total Depth. 3436'
 Comm. 2-3-49 Comp. 3-22-49
 Shot or Treated. acid
 Contractor. Lewis Drilling Company
 Issued. 4-16-49

County. Barton
 KANSAS



CASING:
 8 5/8" 365'
 5 1/2" 3434'

Elevation. _____

Production. Pot. 1780 bbl

Figures Indicate Bottom of Formations.

surface sand & iron	110
shale & iron	180
shale	255
sand & shale	365
red rock	665
lime	685
shale & shells	1345
lime & shale	2710
brown lime	2825
lime & shale	2975
lime	3085
lime & shale	3183
lime	3422
cong. lime	3436
Total depth	

Tops:

Brown Lime	3156
Lansing	3159
Conglomerate	3404
Arbuckle	3433

D. S. T. 3192-3201
 3", open 18" recovered 870' oil

D. S. T. 3216-36, open 45",
 recovered 60' oil & OCM

Perf. 59 3200-3212, G. S. G.
 slight oder 1000 acid then
 perf. flowed in pits 1 1/2 hr.
 Est. 25 BOPH

Bomb test 1780 BO no wtr