

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - C. U. BAY  
Farm - Huschka

No. 4

SEC. 18 T. 20 R. 12W  
NE SE NW

Total Depth. 3551  
Comm. 3-13-49 Comp. 5-2-49  
Shot or Treated. acidized  
Contractor. Lewis Drilling  
Issued. 7-2-49

County. Barton  
KANSAS



Elevation. \_\_\_\_\_

Production. Dry

CASING:

8 5/8" 363'  
5 1/2" 3481'

Figures Indicate Bottom of Formations.

surface sand, clay	112
iron, sand	132
shale, shells	360
red bed	460
red rock, shale	655
limo	680
shale, shells	1665
lime, shale	1860
lime	1950
lime, shale	2535
lime	3055
lime, shale	3190
limo RTD	3493
dolomite	3551
Total Depth	

TOPS:

Brown Lime Lansing	3184	3169
Conglomerate		3424
Arbuckle		3478

Perf. 12 shots @3208-10 no show  
1000 acid, 1 1/2 BW PH rainbow oil  
48 shots 3252-62 no show  
1000 acid  
1 gal oil per hr, 1 1/2 gal wtr per hr  
Perf. 72 shots 3316-28, 1000 acid  
swab 700' wtr in 30 min. no oil  
Perf. 6 shots per foot 3182-96,  
1000 acid no help 24 shots 3252-58  
2000 acid DD 3551 HFW syz/ perf.  
perf. 24 shots 3210-14  
perf. 24 shots 3232-38  
24 shots 3244-48  
2000 acid tested 50' WPH scum oil