

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - C. U. BAY
Farm - Huschka

No. 5

SEC. 18 T. 20 R. 12W
NE SW NW

Total Depth. 3459 RTD
Comm. 5-23-49 Comp. 4-28-49
Shot or Treated.
Contractor. Pickrell Drilling
Issued. 7-2-49

County. Barton



CASING:

8 5/8" 366' com. w/200 sx
5 1/2" 3453' com. w/150 sx

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

| | |
|-----------------------|------|
| sand | 115 |
| pyrite, sand | 125 |
| shale, shells, pyrite | 366 |
| shale | 405 |
| red rock | 665 |
| lime | 680 |
| shale, shells | 1220 |
| salt, sand | 1460 |
| shale, shells | 1560 |
| lime, shale | 2160 |
| shale, lime, shells | 2295 |
| shale, lime | 2475 |
| shale | 2505 |
| lime | 2525 |
| lime, shale | 2855 |
| lime brkn | 2918 |
| lime | 3052 |
| lime, shale | 3185 |
| lime | 3244 |
| lime, shale | 3310 |
| lime RTD | 3459 |
| Total Depth | |
| Slope test and SIM OK | |

TOPS:

| | |
|--------------|------|
| Brown Lime | 3178 |
| Lansing | 3192 |
| Conglomerate | ? |
| Arbuckle | 3452 |

PERF. 48 shots 3194-3202 no
show 1000 acid test 6 GWFH no oil
Perf. 48 shots 3323-32, 1 1/2 BWFH
20 G OBH
Perf. 46 shots 3218-26, 1000 acid,
no oil, no wtr.