


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- ROCKET DRILLING CO., INC.
Farm- Batchman No. 1

SEC. 20 T. 20 R. 12W
SW SW SW

Total Depth. 3484
Comm. 10-13-54 Comp. 1-5-55
Shot or Treated.
Contractor. Rocket Drilling Co., Inc.
Issued. 8-6-55

County Earton
KANSAS



Elevation. 1860 RB

Production. 13 BOPD fr Arb.

CASING:

8 5/8 220' w/ 255 sx cmt.
5 1/2 3453' w/ 125 sx cmt.

Figures Indicate Bottom of Formations

sand	180
shale & shells	665
anhydrite	690
shale	825
shale, shells & salt	1355
lime & shale	1595
lime	1605
sand	1620
lime	1700
sand	1710
lime	1770
sand	1795
lime	1830
lime & shale	1910
sand	1925
lime	2235
lime & shale	2330
shale	2580
lime & shale	2780
lime	3056
lime & shale	3200
shale	3241
lime	3455
Arbuckle	3460
SLM corr. 3460 equals	3456
Arbuckle & shale breaks	3484
Total Depth	

TOPS:

Anhydrite (driller)	661
Heebner	3065
Brown lime	3186
Casing	3202
Arbuckle	3451

No DST's

Ran Schlumberger log.

DP, DD 3476, 11 GOPH, 500 GA dn. csg. no help, DD 3479, some shale, DD 3482, inc. show to 19 GOPH, DD 3484, no inc. 1000 GA dn. csg. no help, ran tbg, sqzd. w/ 57 sx cmt. DC & CO to 3484, SSO, 1000 GA into por. zone 3480-84, 1000 GA 3467-71, swb. load back & swb. 2 BOPH, NW, 14 hrs. pmping. decr. to 15 BOPD in few days. MICT, PB 3430, perf. & tested all zones in L-KC, no oil, drove plugs to btm. & ran tbg w/ packer below L-KC zones back to Arb.