

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- HONAKER-DAVIS DRIG. CO. ET AL  
Farm- Hulme "B" No. 7

SEC. 21 T. 20 R. 12W  
NE SW NW

Total Depth. 3811'  
Comm. 2-6-58 Comp. 2-14-58  
Shot or Treated.  
Contractor. Honaker-Davis Drig.  
Issued. 4-26-58

County Barton  
KANSAS



Elevation. 1840' RB

8 5/8" 242' cem w/200 sx.  
5 1/2" 3510', DV tool set at 2415', 200 sx cem. Production. S W D W  
below & 250 sx. above DV tool.

Figures indicate Bottom of Formations.

top soil & sand	40
sand & gravel	200
blue shale	242
shale & red bed	632
Anhydrite	655
shale & shells	1620
lime & shale	2045
shale & lime	2325
lime & shale	3395
lime	3450
lime & chert	3470
lime, chert, & shale	3565
lime & chert	3811 RTD
Total Depth	

TOPS:

Anhydrite	632
Topeka	2867
Heebner	3042
Brown Lime	3165
Kansas City	3181
Conglomerate	3418
Weathered Arbuckle	3432
Solid Arbuckle	3438

DST #1 packer set at 3440' TD 3450', open  
1 hr. intermittent blow for 25 min.  
recovered 20' slightly oil cut mud.  
no BHP. on 20 minute shut in.