


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. CHAS. HULME DRILLING CONTRACTOR
Farm. Gelwicks No. 1

SEC. 21 T. 20 R. 12W
SE NE NW

Total Depth. 3415
Comm. 3-6-57 Comp. 3-21-57
Shot or Treated.
Contractor. Chas. Hulme Drilling Contractor
Issued. 6-15-57

County Barton
KANSAS



CASING:
8 5/8 @ 215' w/ 250 sx cmt.
5 1/2 @ 3414.5' w/ 75 sx cmt.

Elevation. 1848 KB

Production. 99 bbls.

Figures indicate Bottom of Formations.

clay & sand	200
shale & shells	215
red bed & shale	635
anhydrite	665
shale & shells	1250
shale & lime	1845
lime	2100
shale & lime	2265
shale & shells	2540
lime	2665
shale & lime	2765
shale	2780
lime	3045
shale	3160
lime & shale	3200
lime	3330
lime & shale	3390
lime	3415
Total Depth	

TOPS:
Anhydrite 635
Heebner 3036
Brown lime 3156
Lansing 3173
Conglomerate 3404
Arbuckle 3412

DST #1: 3175-3201, open 30 min. wk.
bl. 6 min. rec. 10' mud, BHP Off

DST #2: 3202-50, open 1 hr. good bl.
rec. 120' gas in pipe, 120' SOC wtry
mud, BHP 960#/20 min.

DST #3: 3293-3318, open 20 min. wk.
bl. 14 min. rec. 10' mud, BHP Off