

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- CHAS. HULME DRLG. CONTR.
 Farm- Gelwicks No. 5

SEC. 21 T. 20 R. 12W
 SE NW NE

Total Depth. 3429' RTD
 Comm. 7-31-57 Comp. 8-8-57
 Shot or Treated.
 Contractor. Chas. Hulme Drlg. Contr.
 Issued. 11-30-57

County Barton
 KANSAS



CASING:
 8 5/8" 286' w/250 sx cem.
 5 1/2" 3421' w/100 sx cem.

Elevation. 1854' KB

Production. 99 BOPD

Figures indicate Bottom of Formations.

sand-red bed	286
red bed-shale	645
anhydrite	665
red bed-shells	1430
shale-lime	1635
lime	2000
lime-shale	2855
lime	3120
lime-shale	3185
lime	3429
Total Depth Rotary	

TOPS:
 Anhydrite 645
 Heebner 3033
 Brown lime 3155
 Lansing 3172
 Conglomerate 3409
 Arbuckle 3419

DST #1--Packer set @ 3175'.
 T.D. 3250'; open 25 mins.;
 strong blow, gas to surface
 in 23 mins. Rec. 30' O & GCM;
 120' HO & GCM; 150' MCO; 180'
 froggy; IFP 150#, FFP 150#, BHP
 750#. Still building.