


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: HONAKER-DAVIS DRILLING CO., et al
Farm: Hulme "A" No. 1

SEC. 21 T. 20 R. 12W
NE NE SW

Total Depth. 3505
Comm. 1-6-57 Comp. 1-15-57
Shot or Treated.
Contractor. Honaker-Davis Drilling Co.
Issued. 7-20-57

County Barton
KANSAS



CASING:
8 5/8 @ 208' w/ 150 sx cmt.
5 1/2 @ 3504' w/ 100 sx cmt.

Elevation. 1856 DF

Production. 328 BOPD

Figures indicate Bottom of Formations.

top soil & sand	40
sand & clay	200
shale & shells	208
shale & red bed	635
anhydrite	670
shale	1150
salt & shale	1240
shale & shells	1450
lime & shale	3505
Total Depth	

TOPS:
Anhydrite 635
Heebner 3033
Brown lime 3154
Lansing 3170
Arbuckle 3402

DST #1: 3172-3200, open 20 min. bl.
2 min. rec. 5' RDM no show oil, BHP
600#.

DST #2: 3403-12, open 1 hr. sl. bl.
rec. 115' mud sl. oil specked thruout
BHP 680# & still building.

DST #3: 3436-45, open 1 hr. gd. bl.
55 min. rec. 210' gas, 1040' clean
oil, BHP 1050#