


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- CHAS. HULME DRILLING
 Farm- Gelwicks No. 7

SEC. 21 T. 20 R. 12W
 SW NE NE

Total Depth. 3422'
 Comm. 11-18-57 Comp. 11-27-57
 Shot or Treated.
 Contractor. Chas. Hulme Drlg.
 Issued. 5-24-58

County Barton
 KANSAS



Elevation. 1832' KB

Production. 79 BOPD

CASING:

8 5/8" 267' cem w/250 sx.
 5 1/2" 3405' cem w/125 sx.

Figures Indicate Bottom of Formations.

sand & gravel	155
sand & shale	267
shale & shells	400
red bed & shale	626
Anhydrite	660
shale & red bed	900
shale & shells	1425
lime	2115
lime & shale	2819
lime	2982
shale & lime	3155
lime	3405 RTD
lime	3422 CTTD
Total Depth	

TOPS:

Anhydrite	626
Heebner	3009
Brown Lime	3128
Lansing	3148
Conglomerate	3386
Arbuckle	3395

DRILL STEM TESTS:

- #1 packer set at 3133', total depth 3200'
 tool open 15 mins., gas to surface in
 2 mins., gauge 2 million CFPD. Rec.
 120' heavily oil cut mud. 300' of oil.
 IFP 250#, FFP 250#, BHP 720# in 20 mins.
- #2 Packer set at 3206', total depth 3222';
 tool open 15 mins., good blow. Rec.
 62' oil & gas cut mud. IFP 0#, FFP 30#,
 BHP 1020# in 20 mins.
- #3 Packer set at 3275', total depth 3292',
 tool open 30 mins., weak blow 7 mins.
 Rec. 30' of mud w/few specks of oil.
 IFP 0#, FFP 0#, BHP 0#.