


KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY COOPERATIVE REFINERY ASSOC. & NORTHERN
ORDNANCE, INC.
FARM Koch "B" NO. 1

SEC. 23 T. 20 R. 12W
LOC. NW NE NE

TOTAL DEPTH 3337 D.F.
COMM. 1-24-51 COMP. 3-2-51
SHOT OR TREATED
CONTRACTOR CRA Tools
ISSUED 4-7-51

COUNTY Barton



CASING

8 5/8" 260' cem. w/200 sx
5 1/2" 3333 cem. w/100 sx

ELEVATION 1801 D.F.

PRODUCTION Phy. Pot. 463 bbls.
oil per day, no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & shale	140
sand, shale & redrock	260
redbed	465
redbed, shale & shells	585
Anhydrite	610
shale & shells	1100
salt & shale	1295
shale & shells	1400
lime & shale	1500
lime	1830
shale & shells-	1870
lime & shale	2786
lime	2989
lime & shale	3202
lime	3338

R. T. D. 3338-3334 D.F.

C. T. T. D. 3337 D.F.

Tops: D. F.

Topeka	2716
Heebner	2962
Toronto	2977
Brown lime	3085
Lansing-Kansas City	3109
Arbuckle	3332

Drilled plug. Filled up 1600'
oil, no water. Drilled deeper
3335. Filled up 1600 oil, no
water. Swabbed 8 1/2 bbls. oil
per hr. Drilled deeper 3337.
Swabbed 10 bbls. oil per hr, no
water. Ran tubing. Acidized
with 500 gallons. Swabbed 15
barrels oil per hour.