


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Buckbee "A" No. 1.

SEC. 24 T. 20 R. 12 W
NE NW SW

Total Depth. 3367'
Comm. 8-3-44 Comp. 8-23-44
Shot or Treated.
Contractor.
Issued. 11-4-44

County. Barton
KANSAS



Rotary O-3348
Cable 3348-67
CASING:
8 1/4" 250' Cem.
6 1/2" 3345' Cem.

Elevation. _____

Production. Min. Well

Figures Indicate Bottom of Formations.

sand	0-100
lime shells & shale	250
shale red & blue	405
shale & red bed	585
anhydrite	610
shale & shells	905
shale & lime	1025
salt & lime shells	1250
shale & lime shells	1465
lime & shale	1610
lime	1670
lime brkn	1695
sand	1705
lime & shale	1745
shale & lime	1760
sand	1775
shale & lime	1815
lime	1865
lime & shale	1905
shale & lime	2020
lime & shale	2330
shale & shells	2505
shale	2590
lime & shale	2795
lime	3015
lime brkn	3080
lime	3200
KC lime	3235
lime	3348
dolomite .lgt sdy	3351
dolomite fine - small amount gry shale	3353
dolomite	3367
Total Depth	

Form Tops DF:
Brown Lansing 3095
Lansing 3112
Base KC 3279
Arbuckle 3343

At 3353 bailed 2 BO --
acidized w/500 gals--
no inc.
At 3367 hole filled 300'
in 10 hrs. -- Acidized
w/500 gals.--swabbed to
bottom -- Hole filled
1400' in 11 1/2 hrs.
Swabbed 22.49 bbls in
6 hrs. after head of
33 bbls was swabbed
off.
Will set pumping unit
& test.