

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Bldg., Wichita, Kansas


Company - BRIDGEPORT OIL CO., INC.
Farm - Buckbee "A" No. 4

SEC. 24 T. 20 R. 12W
SW NW SW

Total Depth. 3379'
Comm. 9-25-48 Comp. 11-8-48
Shot or Treated. Acidized
Contractor.
Issued. 12-4-48

County. Barton

KANSAS



Elevation. _____

Production. Pot. 88 Bbls.

CASING:

8 5/8" 260' cem w/150 sx.
5 1/2" 3356' cem w/150 sx.

Figures Indicate Bottom of Formations.

sand	95	3140-48, slight trace of staining.
shale and shells	260	
redbed, shale, shells	585	3200-12, light stain, fair porosity.
anhydrite	610	
shale, shells	1135	3346-55, fair odor, slight show free oil.
salt and shale	1325	
shale and shells	1480	
lime	1940	ACIDIZATION:
shale, shells	2717	3367'.
lime	2950	Acidized w/500 gals.
shale, lime	3125	Max. press 1375#.
lime	3355	After Acid bailed
dolomite RTD DF	3359	18 gals oil pr hr.
1/2 gal oil pr hr.		3379'
dolomite, tight light stain, some lgt. grn shale no inc. in oil	3361	Acidized w/1000 gals.
hd. tight dolomite w/slight stain & some light green shale, no inc. in oil	3363	Max. press 1175#. Pumped
hd. tight dolomite w/some lgt. grn. shale. slight oil stain	3365	29.45 BO in 8 hrs. for State Phys. Pot of 88 BOPD, no water effective 11-8-48.
Softer crystalline dolomite. trace lgt. grn shale		
1 gal oil pr hr.	3367	
fine xyn dolomite, lgt stain, bailed 23 gal oil pr hr.	3369	
fine xyn dolomite, lgt. stain no inc.	3371	
hd sugary to fine xyn. dolomite w/some blk shale, fair stain no inc. in oil.	3373	
fine xyn. dolomite w/some black shale and trace of chert. fair stain no inc. in oil.	3375	
fine xyn dolomite, some blk. shale, trace chert. fair stain. Bailed 27 gals oil pr hr.	3377	
fine xyn to hd sugary dolomite w/trace black shale and chert. Bailed 33 gals. oil pr hr.	3379	
total depth		

Tops: D.F.

Lansing/Kansas City 3120
Simpson 3346
Arbuckle 3355