

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Buckbee "A" No. 5

SEC. 24 T. 20 R. 12W
S7 S7 S7

Total Depth. 3361'
Comm. 10-6-48 Comp. 11-8-48
Shot or Treated. Acidized w/1000 gals.
Contractor.
Issued. 12-4-48

County. Barton
KANSAS



Elevation.

Production. Pot. 272 BO.

CASING:

8 5/8" 250' cem w/200 sx.
5 1/2" 3347' cem w/150 sx.

Figures Indicate Bottom of Formations.

sand, shale	90
shale, shells	250
redbed, shale, shells	500
shale, shells	585
anhydrite	610
shale, shells	1135
salt, shale	1330
silt, shells	1445
lime	1955
shale, shells	2725
lime	3000
sand, lime	3110
lime	3345
dolomite RTD. DF	3348
1/2 gal oil pr hr.	
hd gran. dolomite, poor stain. Tested 6 GOPH	3353
gran. soft dolomite, fair to good stain, no increase	
	3357
gran. dolomite, soft w/ some lgt. grn shale no increase	3359
hd. gran. dolomite w/some lgt. grn. shale, no inc. Tested 6 GOPH. no wtr.	
	3361
total depth	

Tops: D.F.

Lansing/ Kansas City 3120
Arbuckle 3345

3198-3207, trace of stain.

At total depth 3361'
acidized w/1000 gals, max. press. 1400#. Pumped 90,75 BO, in 8 hrs. for State
Phys pot. of 272 BOPD, no wtr. effective 11-8-48.