

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
P. Scheufler No. 2

SEC. 24 T. 20 R. 12W.
CSL N $\frac{1}{2}$ NW
1320' E 1320' S of NWc

Total Depth. 3350 (cement floor level 3349)
Comm. 1-6-41 Comp. 1-27-41
Shot or Treated.
Contractor.
Issued. 3-15-41

County Barton.



CASING.

103/4" 258' cemented.
6" 3323' cemented.

Elevation.

Production Pot. 1484 B.

Figures Indicate Bottom of Formations. Echometer. No Wtr.

surface sand	186
shale	200
red rock & shale	271
shale & red rock	1308
shale	1418
shale and lime	1503
lime	1570
shale and lime	1911
shale	1970
lime and shale	2226
shale	2607
lime and shale	2705
lime	2776
lime and shale	2837
lime	2882
lime soft	2900
lime	2961
shale and lime	3313
shale	3324
dolomite	3327
lime	3350

Total Depth.

Total Depth from cement floor level 3349

Top of Arbuckle lime from cement floor level 3321.

Total fillup with oil 3000' - Swabbed 78 bbls oil in 3 hours.

1-29-41 acidixed with 2000 gal acid

1-30-41 Established an Echometer potential of 1484 bbls oil-no water.