


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - PHILLIPS PETROLEUM COMPANY
Farm - York Scheufler No. 1

SEC. 24 T. 20 R. 12W
SW SW SE

Total Depth. 3358
Comm. 1-26-49 Comp. 3-30-49
Shot or Treated.
Contractor.
Issued. 5-11-49

County. Barton
KANSAS



CASING:
8" 266'
5" 3342'

Elevation. _____

Production. Phys. Pot. 110 BO,
trace water.

Figures indicate Bottom of Formations.

surface clay	200
shale	285
red bed, shale and shells	584
anhydrite	620
shale, shells	1100
lime, shale	3344
dolomite	3358
Total depth	

Tops:	
Topeka	2703
Heebner	2969
Toronto	2987
Brown Lime	3095
L. Kansas City	3110
Arbuckle	3341

Lansing-Kansas City Zones:

- Zone #1 - 3111-18', poor porosity and trace of stain.
- Zone #2 - 3128-32', Black residual stain.
- Zone #4 - 3148-53, Porosity, possible oil, Electric log interpretation-no samp.)
- Zone #6A - 3178-83' - slight porosity, spotted live oil stain.
- Zone #6 - 3189-99' - fair Porosity, spotted stain to saturation, slight odor.
- Zone #7 - 3239-43' - poor porosity, poor spotted stain.
- Zone #8 - 3258-66' - slight porosity, poor spotted stain.
- Zone #9 - 3274-87, slight porosity, spotted stain, faint odor.