


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - YORK STATE
Farm - Marchand No. 3

SEC. 24 T. 20 R. 12W
CE/2 E/2 NE

Total Depth. 3328'
Comm. 12-27-46 Comp. 1-16-47
Shot or Treated. Acid. w/3500 acid
Contractor.
Issued. 2-22-47 Rotary 0-3311 $\frac{1}{2}$; Cable 3311 $\frac{1}{2}$ -3328

County. Barton
KANSAS



CASING:
8-5/8" 285'
5-1/2" 3313'

Elevation. _____

Production. 100 bbls.

Figures Indicate Bottom of Formations.

sand & clay	0-155
shale & lime shells	180
shale, sand & shells	285
shale & red bed	540
shale & shells	690
salt & shale	730
shale & lime shells	1090
shale & shells	1130
shale & salt	1390
shale & shells	1430
sand & shale	1600
lime & sand	1750
lime	1810
sdv lime	1865
lime	1900
lime brkn & shale	2065
lime & shale	2325
shale & brkn lime	2384
lime & shale	2485
shale & shells	2645
lime	2975
lime & shale	3075
shale	3099
lime	3311 $\frac{1}{2}$
Total Depth (Rotary)	
lime	3328
Total Depth (Cable)	

Tops:
Shawnee 2670
Topeka 2770
Douglas 2990
Kansas City 3095
Arbuckle 3313

Filled up 600' oil in 4 hrs.
after 3500 gal. acid.