


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
505 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILG. CO.
Farm- Schrepel No. 1

SEC. 25 T. 20 R. 12W
SE SW SW

Total Depth. 3368
Comm. 1-18-52 Comp. 1-28-52
Shot or Tested.
Contractor. Birmingham-Bartlett Drilg. Co.
Issued. 3-22-52

County Barton
KANSAS



CASING:

8 5/8" 250' cem. w/235 sx
5 1/2" 3365' cem. w/125 sx

Elevation. 1018 RR

Production. Pmp. 50 BO & NW

Figures indicate Bottom of Formations.

clay & sand	160
sand	190
shells	250
shale & shells	290
red bed	550
anhydrite	565
shale & shells	1100
lime & shale	1885
shale & shells	2215
shale & lime	2385
shale & shells	2520
shale	2705
shale & lime	2800
lime	2990
shale	3015
shale & lime	3115
lime	3331
shale & lime	3365 RTD
shale & lime	3368
Total Depth	

Tops:

Anhydrite	550
Heebner	2990
Brown Lime	3117
Lansing	3130
Arbuckle	3363

C.T.T.D. 3368:

On 1-30-52 Cable tools moved
in and deepened well from
3365' to 3368'. Filled up with
oil 2400' in 6 hrs. Well put on
pump.