

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- LEE DRILLING COMPANY
 Farm- Bryant "C" No. 7

SEC. 26 T. 20 R. 12W
 C N/2 NW SW

Total Depth. 4018
 Comm. 4-14-52 Comp. 5-1-52
 Shot or Treated.
 Contractor.
 Issued. 6-13-53

County Barton

KANSAS



Elevation. 1823

Production. SVDW

CASING:
 8 5/8 600' w/ 400 sx cement
 5 1/2 3514' w/ 25 sx cement

Figures Indicate Bottom of Formations.

sand	170
shale & shells	200
shale & red bed	400
sand & shale	425
red bed, shale & shells	592
anhydrite	620
red bed	760
shale & shells	1485
lime	1645
shale	1660
lime & shale	2575
lime	2695
lime	3038
shale	3135
lime	3375
conglomerate	3456
cherty conglomerate	3490
lime	3570
cherty lime	3640
lime	3745
cherty lime	3805
lime	4018
Total Depth	

TOPS:

Anhydrite 592

SCOUT TOPS:

Heebner 3005
 Brown lime 3135
 Lansing 3149
 Arbuckle 3447