


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY  
Farm - M. Marchland "B" No. 1

SEC. 26 T. 20 R. 12W  
NE SW NW

Total Depth. 3365 $\frac{1}{2}$ '  
Comm. 4-2-49 Comp. 4-28-49  
Shot or Treated. Acidized  
Contractor. Stickle Drlg. Co.  
Issued. 5-28-49

County. Barton  
KANSAS



CASING:  
10-3/4" 597' Cem. W/375 Sx.  
7" 3358' Cem. W/100 Sx.

Elevation. \_\_\_\_\_

Production. Pmp. 456.60 BO, no wtr

Figures Indicate Bottom of Formations.

|                     |                    |
|---------------------|--------------------|
| sand wh             | 160                |
| shale & sand        | 190                |
| shale & shells      | 290                |
| red bed             | 585                |
| shale lime & shells | 1250               |
| salt & shale        | 1330               |
| salt                | 1430               |
| shale & lime        | 1530               |
| lime                | 1915               |
| shale & lime        | 2025               |
| lime & shale        | 2305               |
| shale               | 2445               |
| lime & shale        | 2520               |
| lime                | 2610               |
| shale & lime        | 2715               |
| lime                | 3043               |
| shale               | 3111               |
| K. C. Lime          | 3160               |
| lime                | 3365 $\frac{1}{2}$ |
| Total Depth         |                    |

Rotary total depth 3361'

Tops:  
Anhydrite 587  
Topeka 2721  
Heebner 2987  
Br. Lansing 3111  
Wh. Lansing 3127  
Arbuckle 3357

4-28-49 Drilled plug, filled  
up 300' in one hr. Drlgd.  
4 $\frac{1}{2}$ ' deeper, 1900' fillup  
in 12 hrs.  
4-29-49 Swabbed through  
casing 12 BO, no wtr  
per hr., natural. Acid.  
W/500 gals. 15% acid, Max.  
press. 1700# PSI. 5 mins.  
dropped to 500# PSI. Swb.  
18 BO, no wtr per hr for  
18 hrs thru casing