


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas

Company - PHILLIPS PETRO.
 Farm - Schrepel No. 3

SEC. 26 T. 20 R. 12W
 NE SW NE

Total Depth. 3360
 Comm. 6-7-50 Comp. 7-19-50
 Shot or Treated.
 Contractor.
 Issued. 8-19-50

County. Barton
 KANSAS



CASING:
 8" 290'
 5" 3346'

Elevation. 1811 D.F.
 Draw Down pot.
 Production. 3618 BOPD and no wtr.

Figures Indicate Bottom of Formations.

sand, clay, shells,	
red bed	295
red bed & sand	1159
shale, sand & salt	1498
lime	1844
lime & shale	2330
shale	2548
lime & shale	2718
lime	2923
lime & shale	3113
lime	3360
Total Depth	

Tops:	
Heebner	2973
Toronto	2988
Brown lime	3096
Lansing-K.C.	3112
Arb.	3345

L-Kc. zones.

3114-19, poor xyn. por., trace dead stain.
 3143-49, " vugular " , " blk. residual tar.
 3158-62, " xyn. " , " fair spotted stain.
 3180-88, " vugular & xyn, por., trace spotted stain.
 3195-3206 Fair to good oolitic & oolitic por.,
 trace spotted to even stain., small
 show free oil, slight odor, 60% por. barren.
 3240-51, fair to good oolitic por., fair spotted
 to even stain, trace free oil, slight odor, trace barren por.
 3266-69 Poor xyn & vugular por., trace blk tarry res.
 3279-96, poor to fair oolitic por., trace spotted
 stain, 80% barren por. Ar.
 3345-49, R.T.D. poor xyn por., tr. fair spotted to
 even stain, no odor.